

	BHARAT SANCHAR NIGAM LIMITED (A GOVT. OF INDIA ENTERPRISE) OFFICE OF THE EXECUTIVE ENGINEER (C) BSNL CIVIL DIVISION, DIMAPUR, NAGALAND-797112 OFFICE PH.NO.03862-224935
---	--

No. 23(2)/BSNL/EE/CD/DMP/NIQ/19

Dated: 11.02.2021

The Executive Engineer (Civil), BSNL, Civil Division, Walford, Dimapur-797112 invites for and on behalf of **BHARAT SANCHAR NIGAM LIMITED** wax sealed item rate quotations for the work mentioned below from approved and eligible contractors of DoT/BSNL/CPWD/ State PWD B&R)/DoP/MES/Railways .

Sl.No.	Name of work	Estimated Cost	Time allowed
1	Providing antistatic flooring under NFS-DWDM for additional rooms (Power and Battery room) of ACCESS Node at Rangapahar Army station, Dimapur, Nagaland.	Rs 85277.00	1(one) Month.

1. Last date of receipt of application:- **15/02/2021 upto 13:00 hrs**
2. Date of issue of quotation paper/schedule from the office of the Executive Engineer (Civil), BSNL, Civil Division, Walford, Dimapur:- **upto 13:00 hrs of 16.02.2021.** The schedule of quotation can also be downloaded from our website www.ne2.bsnl.co.in
- 2 The quotation will be received **upto 15.00 hrs on 19.02.2021** and will be opened at **15:30 hrs on the same day.**

Conditons:

1. The time allowed for the work:- 1(one) month from the date of issue of award letter.
2. The quoted rate shall be inclusive of supply, delivery and installation charge at Dimapur or as per the direction of the undersigned.
3. The rate shall be inclusive of applicable GST and labour cess.
4. All suppliers/contractors should have GST registration.
5. Conditional quotation are liable to be rejected.
6. The undersigned reserves the right to reject any or all the quotations without assigning any reasons thereof.


Executive Engineer (Civil)
BSNL, Civil Division
Dimapur.

- Copy To:-
- 1.The SDE(Civil), BSNL, CSD-I/II/III, Dimapur and CSD-Kohima for info.
 2. Notice Board.
 3. File Copy

Executive Engineer (Civil)

SCHEDULE OF QUANTITIES

Name of work:- Providing antistatic flooring under NFS-DWDM for additional rooms (Power and Battery room) of ACCESS Node at Rangapahar Army station, Dimapur, Nagaland.

Sl.No	Description of Item	Qty	Unit	Rate in fig and words	Amount in Fig and words
1	Providing and fixing 2mm thick antistatic PVC flooring sheet of approved brand (Like KRISHNA VYNYL, WONDER FLOOR or equivalent) and shade on smooth and damp proof base using rubber based adhesive like DUNLOP SR or Fevicol Sr 998 or approved equivalent including rolling with light wooden roller etc all complete as per the direction of the Engineer in Charge.	50.00	sqm		
2	Providing and fixing copper strip of size 50x0.20mm below antistatic PVC sheet flooring and fixing with C.P brass screws , making continous contact wih carbon layer of the flooring sheet with the copper strip at joints for making continous conductivity and proper earthing of the flooring and finally connecting the copper strip to the earth points all complete as per the direction of the Engineer in charge.	57.00	meter		
Total:					

(Rate is inclusive of applicable GST and Labour cess)

CONTRACTOR:

EXECUTIVE ENGINEER (CIVIL)