



**BHARAT SANCHAR NIGAM LIMITED
(A GOVT. OF INDIA ENTERPRISE)
OFFICE OF THE EXECUTIVE ENGINEER (C)
BSNL CIVIL DIVISION, DIMAPUR,
NAGALAND-797112
OFFICE PH.NO.03862-224935**

No. 23(2)/BSNL/EE/CD-DMP/NIQ/

Dated: 06.03.2021

NIQ No:-03/EE/BSNL/CD-DMP/2020-21

The **Executive Engineer (Civil), BSNL, Civil Division, Walford, Dimapur-797112** invites for and on behalf of **BHARAT SANCHAR NIGAM LIMITED** wax sealed item rate quotations for the work mentioned below from approved and eligible contractors of DoT/BSNL/CPWD/ State PWD B&R)/DoP/MES/Railways .

Sl.No.	Name of work	Estimated Cost	Time allowed
1	Minor Civil maintenance works to BSNL IQ No. OB 11, Super market, Dimapur, Nagaland.	Rs 36548.00	15(fifteen) days

1. Last date of receipt of application:-**11/03/2021 upto 15:00 hrs**
2. Date of issue of quotation paper/schedule from the office of the Executive Engineer (Civil), BSNL, Civil Division, Walford, Dimapur:-**upto 15:00 hrs of 12.03.2021**.The schedule of quotation can also be downloaded from our website www.ne2.bsnl.co.in
- 2 The quotation will be received **upto 15.00 hrs on 16.03.2021** and will be opened at **15:30 hrs on the same day**.

Conditions:

1. The time allowed for the work:- 15(fifteen) days from the date of issue of award letter.
2. The quoted rate shall be inclusive of supply, delivery and installation charge at Dimapur or as per the direction of the undersigned.
3. The rate shall be inclusive of applicable GST and labour cess.
4. All suppliers/contractors should have GST registration.
5. Conditional quotations are liable to be rejected.
6. The undersigned reserves the right to reject any or all the quotations without assigning any reasons thereof.

**Executive Engineer (Civil)
BSNL, Civil Division
Dimapur.**

Copy To:-1.The SDE(Civil), BSNL, CSD-I/II/III, Dimapur and CSD-Kohima for info.
2. Notice Board.
3. File Copy

Executive Engineer (Civil)

SCHEDULE OF QUANTITIES

Name of work:-Minor Civil Maintenance works to BSNL IQ No. OB-11, Super market, Dimapur, Nagaland.					
S.No	Description of item	Qty	Unit	Rate	Amount
				in fig in words	in fig in words
1	Providing ridges or hips of width 60 cm overall width plain G.S. sheet fixed with polymer coated J. or L hooks, bolts and nuts 8 mm dia. G.I. limpet and bitumen washers complete.				
a)	0.63 mm thick with zinc coating not less than 275 gm/m ²	3.00	m		
2	Providing and applying plaster of paris putty of 2 mm thickness over plastered surface to prepare the surface even and smooth complete.	5.00	Sqm		
3	Distempering with 1st quality acrylic distemper (ready mixed) having VOC content less than 50 gms/litre, of approved manufacturer, of required shade and colour complete, as per manufacturer's specification.				
(a)	Old work (one or more coats)	122.22	Sqm		

(b)	Two or more coats on new work.	5.00	Sqm		
4	Applying one coat of water thinnable cement primer of approved brand and manufacture on wall surface :				
(a)	Water thinnable cement primer.	5.00	Sqm		
5	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade :				
a)	Two or more coats on new work.	39.94	Sqm		
6	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete.	3.51	Sqm		
7	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade :				
(a)	One or more coats on old work.	8.07	Sqm		

8	Providing and fixing C.P. brass bib/Pillar cock of approved quality conforming to IS:8931:				
(a)	15 mm nominal bore.	1.00	No.		
9	Providing and fixing C.P. brass angle valve for basin mixer and geyser points of approved quality conforming to IS:8931 :				
(a)	15mm nominal bore	1.00	No.		
10	Providing and fixing uplasticised PVC connection pipe with brass unions :				
a)	45 cm length				
i)	15 mm nominal bore	1.00	Each		
11	Providing and fixing PTMT grating of approved quality and colour.				
a)	Circular type.				
i)	100 mm nominal dia.	1.00	Each		
12	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings				

	with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in Charge. : Internal work - Exposed on wall				
a)	20 mm nominal outer dia. Pipes.	1.00	m		
13	P/F 30mm thick PVC shutter of supreme/sintex or equivalent with necessary hinges etc complete as per company specifications and as per direction of Engineer in charge.	1.18	Sqm		
14	Supplying standard size doormat of approved quality as per direction of Engineer in charge.	1.00	Each		
15	Dismantling of existing wooden door shutter from frame.	1.00	Each		
16	Credit for old damaged wooden shutter of 0.61*1.93m size.	1.00	Each		

17	Cleaning of floors and wall of toilet and floor of balcony as per the direction of the Engineer in charge.	1.00	Each		
18	Providing Door sill water barrier not less than 12mm thick with cement mortar for balcony/toilet door opening of upto 750mm wide including finishing and patch repairs etc complete as per direction of Engineer in charge.	2.00	Each		
19	Supplying 20 ltr plastic bucket and mug set of approved quality and brand as per direction of Engineer in charge.	2.00	Each set		

(Rate is inclusive of applicable GST and Labour cess)

CONTRACTOR:

EXECUTIVE ENGINEER (CIVIL)