



BHARAT SANCHAR NIGAM LIMITED

(A Government of India Enterprise)

OFFICE OF THE EXECUTIVE ENGINEER (CIVIL)

BSNL CIVIL DIVISION-, Walford, Dimapur 797112

Bharat Sanchar Nigam Ltd.

23(2)/BSNL/ EE/CD-DMP/ NIQ/ 157

Dated 27.09.2021

SHORT NOTICE INVITING SPOT QUOTATION

NIQ No:04/BSNL/CSD-I/DMP/2021-22

The Executive Engineer (Civil), BSNL Civil Division, Dimapur invites for and on behalf of BHARAT SANCHAR NIGAM LIMITED, wax sealed item rate quotations for the work mentioned below from approved and eligible Contractors of DOT/BSNL/CPWD/StatePWD/DOP/ MES/Railways.

Sl no	Name of work	Time allowed
1	Providing antistatic flooring under NFS(ARMY) - DWDM Project at 1 site in Dimapur (Army sites) in Nagaland.(Sub-Head-3:- Providing antistatic flooring for NFS Include at Dimapur, Nagaland.) (Sub-Head:-Supply of materials & fixing at Walford Army camp)	7 (seven) days

1. Last date of receipt of application: 29th September, 2021 up to 1300hrs.
2. Last date of issue of quotation paper from the office of EE(C), Civil Division, Dimapur: 29th September, 2021 up to 1330 hrs. The schedule of quantities can also be downloaded from our website www.ne2.bsnl.co.in
3. The quotations will be received up to 1500 hrs. of 29th September 2021 and the same will be opened at 1530 hrs. on the same day.

Conditions:

1. Time allowed: 7(seven) days from the date of issue of award letter.
2. The quoted rate should be inclusive of GST & Labour cess of 1%.
3. The supplier/contractors should have valid GST registration.
4. Conditional quotations are liable to be rejected.
5. The undersigned reserves the right to reject any or all the quotations without assigning any reason thereof.


Executive Engineer (Civil)
BSNL Civil Division,
Dimapur.

Copy to:

1. The Chief Engineer (Civil), BSNL, NE-II, Civil Zone Dimapur.
2. The Sub Divisional Engineer (civil), BSNL, Civil Sub Division-Kohima/Dimapur-I, II&III.
3. The AGM, IT for publication of NIT in NE2 portal.
4. Notice Board
5. Concerned file


Executive Engineer (Civil)

SCHEDULE OF QUANTITIES

Name of Work:-Providing antistatic flooring under NFS(ARMY) - DWDM Project at 1 site in Dimapur (Army sites) in Nagaland.(Sub-Head-3:- Providing antistatic flooring for NFS Include at Dimapur, Nagaland.)
(Sub-Head:-Supply of materials & fixing at Walford Army camp)

Sl No	Description of items	Qty	Unit	Rate (in fig & words)	Amount (in fig & words)
	Sub Head: FLOORING				
1	Supplying of 2mm thick antistatic PVC flooring sheet of approved brand (like Premier Polyfilm Ltd or equivalent) and shade along with necessary adhesive like Dunlop SR or Fevicol Sr 998 @ 2ltr per 10sqm at Walford Army camp, Dimapur.	32.00	sqm		
2	Supplying of copper strip of size 50x0.20mm and necessary C.P. brass screws.	68.20	metre		
3	Transportation charge for antistatic flooring (30sqm), copper strip(40m) from Guwahati to Walford Army camp, Dimapur.	1.00	job		
4	Fixing of 2mm thick antistatic flooring and shade on smooth and damp proof base using rubber base adhesive like Dunlop SR or Fevicol Sr 998 or approved equivalent, including rolling with light wooden roller etc. all complete as per direction of the Engineer -in- charge.(Rate is exclusive of antistatic flooring material and adhesive etc, which will be paid separately)	59.00	sqm		
5	Fixing of copper strip of size 50x0.20mm below antistatic PVC sheet flooring & fixing with C.P. brass screws, making continuous contact of carbon layer of the flooring sheet with the copper strip at joints for making continuous conductivity and proper earthing of the flooring and finally connecting the copper strip to the earth point all complete as per direction of the Engineer -in-charge.(Rate is exclusive of copper strips an screws etc, which will be paid separately)	103.10	metre		


 Executive Engineer (Civil)